

Balurghat College

(Govt. Sponsored)

(A constituent College under the University of Gour Banga offering both UG & PG Courses)



Dr. Pankaj Kundu
Principal

P.O. Balurghat, Dist. Dakshin Dinajpur,
West Bengal, Pin-733101, India,
Web : balurghatcollege.ac.in

Ph. 03522 255392, Mob. : 8348229018

Email : college.balurghat@gmail.com

Memo no. 25-25/220

Date: 22.09.2025

NOTICE INVITING QUOTATION NO. 81-25/003 (CIVIL) OF 2025-2026 OF THE PRINCIPAL, BALURGHAT COLLEGE, BALURGHAT, DAKSHIN DINAJPUR

Sealed quotations are hereby invited from the bonafied and reliable firms/agencies having experience in executing such type of works as per following terms & conditions.

Name of work: - Repair, Renovation of Balurghat College Building within Campus area at **Departmental Rooms of Philosophy and Commerce** in the district of Dakshin Dinajpur during 2025-2026.

Last date of received of quotation: 06/11/2025 up to 2.00 pm.

Date & time of opening: 06/11/2025 at 4.00 pm.

TERMS & CONDITIONS:-

1. The intending quotations shall have to quote their rates in figure as well as words on their letter head pad. The rate should be including all taxes and charges including GST, Cess etc.
2. No claim what-so-ever will be entertained after acceptance of the rate by the appropriate authority.
3. All intending quotations are advised to inspect the site of work before quoting their rates and get themselves acquainted with the site conditions and quote rates accordingly. No subsequent claim in this regard will be entertained after issue of work order.
4. The guarantee period will be for 1(one) year from the date of completion of the work.
5. The Principal, Balurghat College, Balurghat reserves the right to accept or reject any or all quotations without assigning any reason thereof.
6. The work is to be completed within 30 (Thirty) days from the date of issue of work order.
7. The payment will be made after completion of work. All sites should be cleaned after completion of work by the agencies.

Displayed Schedule of the work in the College Notice Board.

P.K. J. n. 9. 5
Principal
Balurghat College
Principal
Balurghat College

Copy forwarded for information and circulation to:

1. Balurghat College website
2. College Notice Board

SI No.	Description of items.	Unit	Quantity
	(A) PHILOSOPHY & COMMERCE DEPARTMENTAL ROOMS: -		
1	Dismantling R.C. floor, roof, beams etc. including cutting rods and removing rubbish as directed within a lead of 75 m. including stacking of steel bars.	m3	3.00
2	Removing old scales, blisters etc. of interior surface of walls, ceiling by scraping etc. and preparing smooth and even surface with rendering or cement mortar (1:2) (as necessary), to make the surface suitable for receiving distemper. (Payment against this item will be made only when this has been done on the specific direction of the Engineer-in-charge).	m2	530.00
3	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.	m2	315.00
4	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement. (a) Pakur Variety.	m3	3.00
5	Plaster (to wall, floor calling etc) with sand and cement mortar. Including founding off corner and raking out joints or roughening. c) 10 mm thick plaster with (4:1) cement mortar.	m2	145.00
	b) 15 mm thick plaster with (4:1) cement mortar.	m2	170.00
6	Cement washing including cleaning and smoothening surface thoroughly (cement to be used @15 kg./100 sq.m. of surface for one coat and @25 kg./100 sq.m of surface for two coats):a) One coat	m2	315.00
7	White washing including cleaning and smoothening surface thoroughly. b) Two coats	m2	60.00
8	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface. (a) 2 (Two) Coats.	m2	160.00
9	Taking out old damaged tarfelt from the roof, parapet etc. preparing the roof surfaces by removing all spoils, blisters, moss etc. from the working site and disposal of the same beyond the compound and cleaning the site in all respect as per direction of Engineer-in-Charge.	m2	100.00
10	Supplying & laying 3mm thick pre-fabricated plastomeric water proofing membrane conforming to EN 12311-1 & ASTM D 5147, manufactured with atactic poly propylene (APP) modified premium grade asphalt, specially reinforced with non-woven polyester core with polyester reinforcement @160 gms per sqm & both faces covered with thermo-fusible polyethylene film /Mineral on top face over a coat of primer @ 0.40 lit/sqm of manufacturer's specification on smooth, clean dry surface prepared wherever required. Lap joint shall be provided of 75 mm in longitudinal & 100 mm in transverse direction and fused using LPG/ Propane torch employing extra care ensuring full bondage, complete removal of entrapped air and sealing edges into grooves in appropriate manner as per direction of Engineer -in-charge all complete including materials, labour and applicable taxes. (Payment shall be made on the basis of finished surface area.). Membrane Property: Softening Point > 150 deg C, Cold Flexibility < -6 deg C, Tensile Strength, N/cm : 600 (longitudinal), 450 (transverse), Tearing Strength, N: 300 (longitudinal), 200 (transverse)	m2	100.00

P.K.J. 22.9.25
Principal
Balurghat College